COUNTRY : Australia REGISTRATION NUMBER : GROUP REF.: B5
PREF. SUBJECT: PS3
OUESTION N°: 5

Australian Experience of the Benefits of Digital Substations and Measuring Benefits

TransGrid Digital Substations with Process Bus and Station Bus using conventional CTs and VTs:

Grid Projects Implemented:

- 1. AVON Switching station- 3 nos 330 kV bays (Brownfield)
- 2. Stockdill Substation- 330/132 kV sub station (Greenfield)
 - Stage 1 3 nos 330 kV bays, 330/132/11 kV transformer with 11 kV/415V Aux transformer and 132 kV connected feeder bay
 - O Stage 2 Addition of 132 kV bus, 132 kV feeder bays
- 3. 3. Molong 132/66 kV substation

TransGrid Benefits Realisation:

- Asset Management benefits:
 - Reduced assets with less panels
 - Less drawings with greater use of Fibre LAN
 - Operation and maintenance improvements with more monitoring and fault records easier to configure
- Cost effective
 - Saving in with fibre and less copper cabling
 - Less trenching requirement/costs,
 - Smaller building so less building costs
- Time and Resource Efficient
 - Reduction in construction effort and time
 - Faster and efficient overall augmentation with work in parallel and less testing
 - Study Case **Stockdill augmentation** (next slide)

TransGrid Study Case – Stockdill augmentation

- Reduction in construction and commissioning effort and time
- Outdoor works related to secondary systems were limited to:
 - ➤ installation of outdoor boxes with MU and connections to primary plant.
 - Fiber duct laid to nearest fiber pit with spare ducts to control building
 - Fiber cable laid from MUs to FO Marshalling panel
- IEDs plugged into control panel
- Network configurations done @ lab and implemented live line @ sub

Endeavour Energy Goals & Outcomes for 2019 Digital Substation

- Goals:
 - Reduction in the cost of greenfield substation construction
 - Reduction in the whole of life maintenance cost of substations

- Improved construction efficiency
- Improved reliability
- Agile approach to react to changing network loads and connections efficiently

Outcomes:

- Modular buildings provided savings of \$5.5M
 A reduction in copper cabling and installation provided savings \$0.4M
 A reduction in protection and control panels provided savings of\$0.25M
 Modular Buildings provided 9 months time savings compared to traditional civil and building construction